



Project No. & Name:	Addendum No.:	2
1095226-273630- Water Meter Chamber	No. of Pages:	1
	Date:	April 25, 2024
	Doc. No.:	P2704-1059386316-90(1.0)

The following change(s) in the Tender Documents are effective immediately.
This Addendum forms part of the Contract Documents.

ITEM	DESCRIPTION	ACTION
2.1	Q. Are we to carry costs to replace the components inside the chamber? A. Yes. Those components mentioned in the Report.	
2.2	Q. Is the proposed bypass to include the existing chamber? A. No. The bypass is located near the future BFPV. The contractor is to include valves for the bypass.	
2.3	Q. Please confirm if gate valve replacement is part of scope – mentioned in RFT documents but not noted on drawings/specifications. A. Yes. Please see the Report in conjunction with the drawings.	
2.4	Q. Please quantify approximate length of cracking in existing water meter chamber. A. These are small cracks and require patching and repairs. A seepage protection should be ensured. This includes establishing a drain in the Chamber floor.	
2.5	Q. Confirm asphalt restoration scope – will this work be performed as required? If not, please quantify extent of concrete restoration; detail 3 on dwg C2.0. A. Any asphalt damaged during the construction is to be repaired. Any concrete sidewalk damaged during construction is to be repaired. Any foundation wall concrete or interior concrete blocks damaged or drilled during construction are to be repaired.	

Colliers Project Leaders Inc. Date: April 25, 2024

Distribution: All Bidders
 File